



Haryana Government Gazette

EXTRAORDINARY

Published by Authority

© Govt. of Haryana

No. 44-2024/Ext.] CHANDIGARH, THURSDAY, MARCH 14, 2024 (PHALGUNA 24, 1945 SAKA)

HARYANA GOVERNMENT
PUBLIC WORKS DEPARTMENT
(BUILDING AND ROADS BRANCH)

Notification

The 14th March, 2024

No. E-in-C/PWD (B&R) / Chandigarh DC/02 dated 14/03/2024 -

THESE AMENDMENTS WILL BE APPLICABLE FROM THE DATE OF GAZETTE NOTIFICATION.

Addenda and Corrigenda to the Haryana PWD Schedule of Rates 2021 (Third Edition)

A&C Slip No.12

Dated: 14/03/2024.

The rates of the following items provided in HSR - 2021 were discussed and have been approved to be added/amended as under:

Sr. No.	HSR Item no.	Amended Description of item	Unit	Amended Rates required in HSR (2021) by correction in calculation.			
				Labour rates	Machinery rates	Material rates	Through rates
1.	17.25.1	Prime Coat @ 0.60kg per sqm Providing and applying primer coat with bitumen emulsion on prepared surface of granular Base including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means as per technical clause 503 of MORT&H specifications	Sqm	0	3	27	30

Sr. No.	HSR Item no.	Amended Description of item	Unit	Amended Rates required in HSR (2021) by correction in calculation.			
				Labour rates	Machinery rates	Material rates	Through rates
2.	17.27.3	Providing and laying bituminous macadam 80-100 mm Continuous type hot mix plant 40-60 TPH using crushed aggregates of specified grading premixed with bituminous binder VG -30 @3.3% transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction complete as per technical clause 504 of MORT&H specifications. Note: - If bitumen required is more than 3.3% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.	Cum	50	913	4495	5758
3.	17.27.4	Providing and laying bituminous macadam 50-75 mm thick with Continuous type hot mix plant 40-60 TPH using crushed aggregates of specified grading premixed with bituminous binder VG -30 @3.4% transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction complete as per technical clause 504 of MORT&H specifications. Note:- If bitumen required is more than 3.4% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.	Cum	50	913	4906	5869
4.	17.30.2	Providing and laying 50mm - 75 mm dense graded bituminous macadam with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified	Cum	53	813	6586	7452

Sr. No.	HSR Item no.	Amended Description of item	Unit	Amended Rates required in HSR (2021) by correction in calculation.			
				Labour rates	Machinery rates	Material rates	Through rates
		grading, premixed with bituminous binder VG 30 @ 4.5% by weight of total mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction complete, as per technical clause No. 505 of MORT&H specifications. Note:- If bitumen required is more than 4.5% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.					
5.	17.31.1	Providing and laying 50 mm - 65 mm bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder VG - 30 @ 5.2% per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction complete in all respects as per technical clause 507 of MORT&H specifications as per MORTH specification. Note:- If bitumen required is more than 5.2% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.	Cum	54	891	7560	8505
6.	17.31.2	Bituminous Concrete 30 mm to 45 mm thickness (grading II) with 100-120 TPH batch type HMP Providing and laying 30 mm - 45 mm bituminous concrete	Cum	54	830	7793	8677

Sr. No.	HSR Item no.	Amended Description of item	Unit	Amended Rates required in HSR (2021) by correction in calculation.			
				Labour rates	Machinery rates	Material rates	Through rates
		with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder VG - 30 @ 5.4% per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction complete as per technical clause 507 of per MORTH specifications. Note:- If bitumen required is more than 5.4% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.					
7.	17.32.3	Surface Dressing Providing and laying surface dressing as wearing course in single coat using crushed stone aggregates of specified size on a layer of bituminous binder VG - 10 laid on prepared surface and rolling with 8-10 tonne smooth wheeled steel roller complete as per technical clause 509 of MORT&H specifications. 13 mm nominal size chipping with Bitumen	Sqm	1	6	58	65
8.	17.43.1	Providing & laying 50 mm - 75 mm DBM using the reclaimed material to the extent of 30% per cent of the required quantity after carrying out necessary check and evaluation, adding fresh material including rejuvenation as required, grade, level and thickness, all as specified in clause No.519. (5th revision) 2013 using bitumen VG-30 (minimum Bitumen content 4.50% i/c bitumen of retrieved material as per job mix	Cum	49	698	5725	6472

Sr. No.	HSR Item no.	Amended Description of item	Unit	Amended Rates required in HSR (2021) by correction in calculation.			
				Labour rates	Machinery rates	Material rates	Through rates
		formula) using 100-120 TPH batch type hot mix plant with appropriate arrangement for use of R.A.P, appropriate roller and with hydraulic paver finisher with sensor control to the required grade. Note:- If bitumen required is more than 4.50% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.					
9.	17.43.1.1	Providing & laying 80-100 mm DBM using the reclaimed material to the extent of 30% per cent of the required quantity after carrying out necessary check and evaluation, adding fresh material including rejuvenation as required, grade, level and thickness, all as specified in clause No.519. (5th revision) 2013 using bitumen VG-30 (minimum Bitumen content 4% i/c bitumen of retrieved material as per job mix formula) using 100-120 TPH batch type hot mix plant with appropriate arrangement for use of R.A.P, appropriate roller and with hydraulic paver finisher with sensor control to the required grade. Note:- If bitumen required is more than 4.00% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.	Cum	49	698	5209	5956
10.	17.43.3	Providing & laying 80-100 mm BM using the reclaimed material to the extent of 30% per cent of the required quantity after carrying out necessary check and evaluation, adding fresh material including rejuvenation as required, grade, level and thickness, all as specified in clause No.519. (5th revision) 2013 using bitumen VG-30	Cum	49	638	4030	4717

Sr. No.	HSR Item no.	Amended Description of item	Unit	Amended Rates required in HSR (2021) by correction in calculation.			
				Labour rates	Machinery rates	Material rates	Through rates
		(minimum Bitumen content 3.3% i/c bitumen of retrieved material as per job mix formula) using 40-60 TPH Drum type hot mix plant with appropriate arrangement for use of R.A.P, appropriate roller and with hydraulic paver finisher with sensor control to the required grade. Note:- If bitumen required is more than 3.3% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.					
11.	17.43.4	Providing & laying 50-75 mm BM using the reclaimed material to the extent of 30% per cent of the required quantity after carrying out necessary check and evaluation, adding fresh material including rejuvenation as required, grade, level and thickness, all as specified in clause No.519. (5th revision) 2013 using bitumen VG-30 (minimum Bitumen content 3.4% i/c bitumen of retrieved material as per job mix formula) using 40-60 TPH Drum type hot mix plant with appropriate arrangement for use of R.A.P, appropriate roller and with hydraulic paver finisher with sensor control to the required grade. Note:- If bitumen required is more than 3.4% as per job mix formula, no extra payment will be paid. Extra bitumen required will be considered as incidental to work.	Cum	49	728	4128	4905

A&C Slip No.13**Dated: 14/03/2024.**

Regarding various items used in construction works following brands shall be inserted for respective category in the Common Bidding document in the General Conditions of contract :

1. TMT Steel : After Electrosteel the following brand names shall be added :
Shyam Steel Industries Ltd. / OMPL (Orissa Metallurgical Industry Pvt. Ltd.), Super Shakti Steel etc.
2. Ceiling solutions : The following brand names shall be added :
Armstrong, Gyproc, Decibel Ceiling & Acoustics, *Shera*, *USG Boral* and *Gypsoman* etc.
3. Paint works like Exterior emulsions, ACRYLC interior emulsion / water-based enamels / enamel and distempers the following brand names shall be added :
Asian Paint, Dulux, Nippon, Nerolac, Berger and Woodco paints etc.
4. For WPC door frames, doors and windows etc. the following brand names shall be added :
Green, Duro, Durenzo, Century, COBE etc.

NAVNEET NAIN,
Convener, Central Zonal Committee,
Haryana PWD Schedule of Rates-cum-
Superintending Engineer, Ambala Circle,
PWD (B&R), Ambala Cantt.